VP-20: DOOR SENSOR CHECK (pg 1 of 1)



Time: 1 minute

Purpose: To verify that Door Sensor operates properly

- Close door.
- 2. Enter Carousel Door Hand Controls:
 - MONITOR
 - HND CNTL
 - OTHER
 - CRSL_DOOR

Display shows: Lamp Test in progress.

- 3. Display shows (on right side): DR = C
- 4. Open door: DR = O
- 5. Close door:

DR = C

5 Verification Procedures VP-20: Door Sensor Check LCx® Analyzer Service Manual (Text P/N 47278-102)

Chapter Manual CD Main Index Contents Contents Screen

5 - 53